

BRUHAT BANGALORE MAHANAGARA PALIKE


Item No. 57

"APPROVED SCHEDULE - B"

Tender Notification No: BBMP/ EE /Btp/Ten/02/2012-13 Dated: 15-05-2012

Name of Work: Improvements to Roads and Drains in Chikkabettahalli Slum area and MS Palya areas in Ward No. 11 Kuvempunagara.

Sl. No.	Approved Qty.	Description	Unit	Approved Rat3s	
				In Figures	In Words
1	87.02	KSRRB 300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3. Page No. 149/ Item No. 19.1/ PWD SR 2011-12	Cum	65.95	Rupees Sixty Five And Paise Ninety Five Only
2	53.06	KSRRB 300-2 : Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3 Page No. 149 / Item No. 19.2/ PWD SR 2011-12	Cum	91.32	Rupees Ninety One And Paise Thirty Two Only
3	87.02	KSRRB M300-53. Construction of embankment with approved materials Gravel/Murum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement Table 300-2 complete as per specifications. which includes cost of gravel / Murum, watering charges & compaction by vibratory roller) PWD SR 2011-2012 Bangalore circle Pg No. 156, I No. 19.60	Cum	154.09	Rupees One Hundred Fifty Four And Paise Nine Only
4	98.81	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 Kgs using 40mm and down size graded granite metal, coarse aggregates @ 0.85 cum and fine aggregates @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P.12/I.4.3 PWD SR - 2011-12)	Cum	4132.84	Rupees Four Thousand One Hundred Thirty Two And Paise Eighty Four Only
5	235.80	KSRB 4-6.4: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 (P.17 / I.4.31 PWD SR - 2011-12)	Sqm	232.27	Rupees Two Hundred Thirty Two And Paise Twenty Seven Only



Sl. No.	Approved Qty.	Description	Unit	Approved Rat3s	
				In Figures	In Words
6	23.58	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459 cum wuth superplastisier @ 3lts confirming to IS 9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, wall (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.6 (P.13/I.4.11 PWD SR - 2011-12)	Cum	5556.82	Rupees Five Thousand Five Hundred Fifty Six And Paise Eighty Two Only
7	15.33	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 Page No. 19/ Item No. 4.46/ PWD SR 2011-12	Qtl	7708.60	Rupees Seven Thousand Seven Hundred Eight And Paise Sixty Only
8	58.01	KSRB- 4-1.5 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300 kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.64 cum and fine aggeregares @ 0.43 cum with superplastisier @ 3lts confirming to IS9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification. No. KBS 4.1,4.2, No. 12/ Item No. 4.5/ PWD SR 2011-12	Cum	5234.59	Rupees Five Thousand Two Hundred Thirty Four And Paise Fifty Nine Only
9	119.06	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means inclcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123)	Cum	76.28	Rupees Seventy Six And Paise Twenty Eight Only

S. P. Nagaraj
Signature of the Contractor

[Signature]
Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92